

	KL	TL	EL
Approvals			
NSF - C2	●	●	
UL + CUL - Wet Location	●	●	●
ISO Rated	● 3 >	● 5 >	● 7 >
IP Rated	● 66	● 65	● 64
Class I Div II Group A, B, C, & D	◇		◇
Class II Div II Group F, & G	◇		◇
Class III	◇		
Federal Standard 209 E	● 1	● 100	● 1,000
HD 1700 - 1700 PSI Hose Down	◇	●	
HD 85 - 85 PSI Hose Down	◇	●	◇
NSF - 49 Pressurized Leakage Test	●	●	

Construction			
NSF Listed Gasket System	●	●	◇
100% Pure Neoprene Gasket			●
Agion™ Anti Microbial Finish	◇	◇	◇
Channel Inset Door			●
One Piece Inset Door		●	
Overlapping One Piece Inset Door	●		
Smooth Surface Extruded Lens	●	●	●
100% Pure Virgin .135 P12 Acrylic	●	●	●
Tig Welded 1 Piece Hole Free Housing	●	●	●
Made in USA / IBEW Union Label	●	●	●

Installation			
Toggle Arm Mounting System	●	●	●
1 - 1.5 T-Bar Mounting System	●	●	●
Four flattened & sealed knockouts	●	●	●
Screwless Door Frame	◇		
Top Relamp	◇		●
Plenum Access	◇		
Earthquake Clips for Seismic Support	◇	●	●
Yoke Mounting	◇	◇	◇