

8
THIS DRAWING APPLIES FOR THE FOLLOWING
"F" HOUSING CRM
EL-F
WL-F
TL-F
ML-OF
ML-EF

CRM DETAILS FOR "F" HOUSING ONLY

NOTE: THE WIDTH OF THE CEILING CUTOUT IS CONSTANT AND DOES NOT CHANGE. TO CALCULATE THE LENGTH OF THE CUTOUT YOU WILL NEED TO USE THE FORMULA PROVIDED IN THE UPPER RIGHT HAND CORNER. EXAMPLES ARE PROVIDED BELOW AS A REFERENCE. IT IS VERY IMPORTANT TO VERIFY THAT THIS IS THE CORRECT SET OF INSTRUCTIONS FOR YOUR LUMINAIRE PLEASE CONSULT THE KURTZON SALES ORDER AND COMPARE THE MODEL SERIES TO THAT IN THE UPPER LEFT HAND CORNER OF THIS PAGE.


Cutout Formula for Hole Length			
Fixture Size	Fixture Qty	Dimension	Extended Dimension
1x4	A	48.07"	A x 48.07"
OFFSET	NA	NA	0.50"
Total cutout Length =		[A x 48.07"] + .50"	

EXAMPLE CALCULATION (2) 1x4 FIXTURES

CUT LENGTH = [(# OF 1X4 FIXTURES) x (48.07") + 0.50"]




CUT LENGTH = [(2) x (48.07")] + .50"

CUT LENGTH = [96.14"] + .50" = **96.64"**



APPLY SILICONE AROUND PERIMETER OF THE ENDS. BY OTHERS.

NUT, GASKET, WASHER, 1/4-20 X 0.750 PH SCREW. SUPPLIED BY KURTZON.



This drawing and all information on it is, unless otherwise stated, the property of Kurtzon Lighting. Reproduction or retransmission of the materials, in whole or in part, in any manner, is prohibited without the prior written consent of Kurtzon Lighting.			
SCALE: DO NOT SCALE	DESCRIPTION:	PART #:	
	APPROVED BY:	APPROVED DATE:	DRAWN BY: RefugioR
			DATE: 8/22/2017
TOLERANCES: UNITS: INCHES ANGULAR BEND ± 2° ANGULAR MACH ± .5° 0.0 ± .05 0.00 ± .015 0.000 ± .005	MATERIAL: MAKE TO ORDER	REV: 0	SHEET: 3
KURTZON LIGHTING 1420 S TALMAN AVE CHICAGO, IL 60608 WWW.KURTZON.COM			